

Responsibility of Project Partner

3 Project

31 Preliminary Project	Architect	Engineer	Contractor	TS3
Training planning and engineering				х
Pre-dimensioning		х		Support
Structural consultancy				х

32 Construction Project	Architect	Engineer	Contractor	TS3
Structural design planning		х	(x)	Support
 Kick-off meeting with TS3 is mandatory (construction process, propping concept, etc.) 				
Erection planning		х	(x)	Support
Kick-off meeting with TS3 is mandatory				
(work coordination, scheduling, etc.)				
Information transfer for verification				
Structural design planning of relevant		×	(x)	Recipient
structural components (build-up and				
detail catalogue, etc.)		x	(x)	Recipient
Erection planning of CLT (positioning				
plans, erection plans, etc.)				

4 Invitation to Tender

41 Invitation to Tender, Offer Comparison,	Architect	Engineer	Contractor	TS3
Tendering of TS3-relevant items	х	х	(x)	Support
Information transfer for verification • Bill of quantities	х	х	х	Recipient
CLT producer			X	Recipient
CLT processing facility			X	Recipient
Tender for TS3 technology			Recipient	Х
Consultancy regarding TS3 technology				х
Contract agreement for TS3 services			х	х



5 Implementation

51 Execution planning	Architect	Engineer	Contractor	TS3
 CLT planning Definition of CLT requirements Definition of panel thickness Definition of panel build-up Orientation of face layers Positioning of TS3 joints Joint geometry for TS3 joint Propping concept 	X	X	Recipient	Support
Information transfer for verification QA document for CLT design QA document for approval check of CLT production data Propping concept		x x		Recipient Recipient Recipient
Shop planning for CLT and TS3 joints		х	х	Support
Information transfer for verification CLT production data CLT assembly plan		Approval	x x	Recipient Recipient
Material order CLT TS3 technology			x x	

52 Execution	Architect	Engineer	Contractor	TS3
Scheduling coordination for CLT processing and assembly			х	
Training for execution of TS3 technology				х
Pre-treatment			Optional	х
Acceptance of pre-treatment			Optional	х
Ensuring site accessibility			х	
CLT assembly			х	
Acceptance CLT assembly			Optional	х
TS3 bonding of CLT panels			Optional	х
Acceptance of TS3 bonding of CLT panels		Optional	Optional	х



53 Commissioning, completion	Architect	Engineer	Contractor	TS3
 Final report / documentation Deficiency list Quality assurance report 		Recipient Recipient Recipient	Recipient Recipient Recipient	x x x